



GENERAL SIDEWALK LAYOUT PLAN




GENERAL SHARED USE PATH LAYOUT PLAN




SECTION B-B
ISOLATION JOINT


NOTE: A GRADE BREAK SHOULD NOT BE PLACED BETWEEN THE TURNING SPACE AND BOTTOM OF RAMP, UNLESS A LANDING IS REQUIRED FOR SIGNAL PUSH BUTTONS, OR IN THE CASE OF LONG RAMP. GRADE SHOULD GENERALLY BE CONSTANT BETWEEN GRADE BREAK AT BOTTOM OF RAMP AND TURNING SPACE.




SECTION C-C
CONTRACTION JOINT
(SAWED OR FORMED)




SECTION D-D
SIDEWALK TO INLET DOWELING DETAIL




SECTION A1-A1



SECTION A2-A2



MEDIAN RAMP CROSSING PLAN



SECTION E-E

SIDEWALK GENERAL NOTES

- CONSTRUCTION JOINTS SHALL BE PLACED IN 5'-0" WIDE SIDEWALKS AT A MINIMUM OF 5'-0" INTERVALS. WHEN OTHER WIDTHS OF SIDEWALK ARE USED, CONSTRUCTION JOINTS SHALL BE PLACED AS DIRECTED BY THE CITY ENGINEER OR AN AUTHORIZED REPRESENTATIVE.
- ISOLATION JOINTS SHALL BE PLACED AT ALL LOCATIONS WHERE SIDEWALK ABUTS EXISTING STRUCTURES AND AS DIRECTED BY THE CITY ENGINEER OR AN AUTHORIZED REPRESENTATIVE.
- ACCESS RAMP SHALL BE CONSTRUCTED AT ALL LOCATIONS WHERE SIDEWALKS INTERSECT NEW STREET CONSTRUCTION AND AS OTHERWISE SHOWN ON THE PLANS.
- ALL SHARED USE PATH JOINTS SHALL BE SAW CUT.
- ALL SIDEWALKS AND RAMP MUST BE CONSTRUCTED TO CURRENT PROWAG STANDARDS.
- THERE SHALL BE NO GRADE BREAKS ON THE RAMP. GRADE SHOULD BE CONSTANT BETWEEN GRADE BREAK AT BOTTOM OF RAMP AND TURNING SPACE.
- SIDEWALK CURB FOR ADA COMPLIANCE IS SUBSIDIARY TO THE RAMP.
- GRADING REQUIRED TO FACILITATE DRAINAGE BETWEEN THE SIDEWALK AND CURB IS SUBSIDIARY TO THE RAMP.

2025 EDITION

SHEET ____ OF ____

DATE	BY	REVISION
04-01-25	LJM	REPLACES ALL PREVIOUS VERSIONS OF CONCRETE SIDEWALK ACCESS RAMP DETAILS
07-07-22	LJM	ALLOWS FOR THE USE OF CONCRETE-FIBER-REINFORCEMENT IN RAMP



STANDARD DETAILS FOR
CONCRETE SIDEWALK AND SHARED USE PATH LAYOUTS

DAVID P. CRONIN
CITY ENGINEER


CRAIG S. OWENS
CITY MANAGER



- NOTES
- RAMP WITH RADIAL DETECTABLE WARNING
1. FLARED SIDES SHALL BE 10% OR FLATTER SLOPE, IF ADJACENT TO SIDEWALK, AND 25% OR FLATTER SLOPE, IF ADJACENT TO LANDSCAPED AREAS.
 2. IF THE SPECIAL SHAPING DISTANCE EXCEEDS 5' FROM THE BACK OF CURB, THEN REFER TO THE "BLENDED TRANSITION DETECTABLE WARNING SURFACE DETAIL". IF USING RADIAL DETECTABLE WARNINGS, BLENDED TRANSITION SHOULD HAVE A 4% OR FLATTER SLOPE.
 3. DETECTABLE WARNING DOMES SHALL BE ALIGNED PERPENDICULAR TO THE GRADE BREAK BETWEEN THE RAMP RUN AND STREET, UNLESS A BLENDED TRANSITION AND USING RADIAL DOMES.
 4. DETECTABLE WARNINGS SHALL CONTINUOUSLY EXTEND FOR A MINIMUM OF 24" IN THE PATH OF TRAVEL.
 5. DIMENSIONS SHOWN IN THIS DRAWING ARE TARGET DESIGN VALUES. ALL SIDEWALKS AND RAMPS MUST BE CONSTRUCTED TO CURRENT PROWAG STANDARDS.
 6. IF GRADES DO NOT ALLOW RAMP TO BE CONSTRUCTED BASED ON SLOPES SHOWN, OVERALL LENGTH MAY BE LIMITED TO 15'. EXACT LIMITS TO BE APPROVED BY THE ENGINEER.
 7. COMPACTED SUBGRADE SHALL BE CLEAN, LEVELED WITH AN APPROPRIATE MATERIAL, AND COMPACTED.
 8. THE TERMS "RAMP" AND "BLENDED TRANSITION" REFER TO THE GEOMETRIC REQUIREMENTS OF PROWAG, NOT PAY ITEMS. THE FIRST 6'-0" OF A RAMP OR BLENDED TRANSITION SHALL BE "REINFORCED CONCRETE SIDEWALK". BEYOND 6'-0", THE RAMP OR BLENDED TRANSITION, SHALL BE "CONCRETE SIDEWALK". DETECTABLE WARNINGS SHALL BE MEASURED SEPARATELY.
TYPICAL BID ITEMS ARE:
 - CONCRETE SIDEWALK (4"), SY
 - CONCRETE RECREATIONAL PATH (6" FIBER REINFORCED), SY
 - TYPICAL CONCRETE SIDEWALK AND RETAINING WALL LF
 - REINFORCED CONCRETE SIDEWALK (ADJACENT TO CURB), SF
 - DETECTABLE WARNING PANELS, SF
 - DETECTABLE WARNING PANELS (RADIAL, XX FT. RADIUS), SF
 - CONCRETE MEDIAN REINFORCED SIDEWALK CROSSING, SF
 9. SIDEWALK CURB FOR ADA COMPLIANCE IS SUBSIDIARY TO THE RAMP.
 10. GRADING REQUIRED TO FACILITATE DRAINAGE BETWEEN THE SIDEWALK AND CURB IS SUBSIDIARY TO THE RAMP



2025 EDITION		SHEET _____ OF _____
DATE	BY	REVISION
04-01-25	LJM	REPLACES ALL PREVIOUS VERSIONS OF CONCRETE SIDEWALK ACCESS RAMPS DETAILS
07-07-22	LJM	ALLOWS FOR THE USE OF CONCRETE-FIBER-REINFORCEMENT IN RAMPS



STANDARD DETAILS FOR

CONCRETE SIDEWALK ACCESS RAMPS

2 OF 2

DAVID P. CRONIN CITY ENGINEER	CRAIG S. OWENS CITY MANAGER
---	---------------------------------------